



A VISUAL GUIDE TO ACCESSIBILITY REQUIREMENTS

SINGLE STALL RESTROOMS*

ICC/ANSI A117.1, 2003 EDITION:



Door cannot swing into wheelchair turning space except where the room is for individual use and a clear floor area of 30" x 48" is provided within the room, beyond the arc of the door swing.

304.3.1 Circular Space.

The turning space shall be a circular space with a 60" minimum diameter. The turning space shall be permitted to include knee and toe clearances.

603.2.2 Overlap.

Clear floor spaces, clearances at fixtures, and turning spaces shall be permitted to overlap.

603.2.3 Door Swing.

Doors shall not swing into the clear floor space or clearance for any fixture.

Exception: Where the room is for individual use and a clear floor space complying with section 305.3 is provided within the room beyond the arc of the door swing.

305.3 Size.

The clear floor space shall be 48" minimum in length by 30" minimum in width.

604.2 Location.

The water closet shall be located with a wall partition to the rear and to one side.

The centerline of the water closet shall be 16" minimum to 18" maximum from the side wall or partition for single use restrooms.

604.3.1 Size.

A clearance around a water closet 60 inches minimum, measured perpendicular from the sidewall, and 56 inches minimum, measured perpendicular from the rear wall, shall be provided.

See hatched area.


604.3.2. Overlap.

The required clearance around the water closet shall be permitted to overlap the water closet, associated grab bars, paper dispensers, sanitary napkin receptacles, coat hooks, shelves, accessible routes, clear floor space at other fixtures and the turning space. No other fixtures or obstructions shall be within the required water closet clearance.

*While considerable effort has been made to ensure the accuracy of the graphic information presented, the City of Norman assumes no responsibility for errors or omissions in the information presented for use within this municipality.

604.5.1 Fixed Side Wall Grab Bars.

Water supply and drain pipes under lavatories and sinks shall be insulated or otherwise configured to protect against contact. There will be no sharp or abrasive surfaces under lavatories and sinks.



ANSI Restroom Page 2/Drawn by C Callahan, 01/2010